CHALLAKERE MUNICIPALITY.

Notification.

(1) Notice is hereby given that sealed tenders for improving the existing old drains in Challakere Municipality, will be received in the Office of the President, Challakere Municipality, up to 5 P.M., on Saturday, 15th September 1928.

(2) The approximate quantity and description of work required to be done, are given in the subjoined statement and tenders should be sent in the form of that statement duly filling in the column left blank, the rate at which each item of work will be executed. The tenders should be superscribed, "Tender for the improving the existing old drains in Challakere Town," in default of which tenders will be rejected.

(3) Earnest money of Rs. 150 which should be in cash or currency notes should accompany the tender without which tenders will not be considered.

(4) The plan and detailed estimate may be seen at the Office of the President, Challakere Municipality, between the hours of 12 noon and 5 P.M. on all working days.

(5) The final acceptance of any tender will rest with the Municipal Council, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

(6) Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond on stamped paper, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

(7) The name of the successful competitor whose tender has been accepted will be posted on the notice board in the President's Office in due course.

(8) No enquiries regarding the acceptance or rejection of a tender will receive any reply.

(9) On acceptance of one of the tenders, the earnest money on rejected tenders will be refunded.

(10) Charges on account of implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid separately, but should be borne entirely by the contractor.

(11) Rates for non-tendered and non-estimated items shall be as per schedule rates of the municipality or those fixed by the Municipal Council after working out data with not more than 10 per cent contractor's profit.

(12) In all matters not specially provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind the decision of the Municipal Council of Challakere, will be final and legally binding.

(13) The work should be completed before the end of January 1929.

Serial No.	Description of work	Unit	Quantity	Rate
				Rs. a. p.
1	Removing old and worn out mortar and bricks ..	R.ft.	2,898	
2	Surki jelly concrete	C.ft.	1,403	
3	½" cement plastering	Sqr.	62·12	
4	Cement pointing	„	47·10	
5	Replacing missing stones set in mortar ...	R.ft.	396	
6	Removing and refixing covering slabs at road crossing.	S ft.	100	
7	Earthwork excavation for foundation	C.yds.	3	
8	Construction of walls with burnt stone in surki mortar.	C.ft.	45	
9	Burnt stone slabs (4" thick)	S.ft.	50	
10	Chunam pointing	Sq.	6·25	
11	Silt traps 1/8" cast iron set in surki concrete cement plastering, complete (1½'×9").	Each	No. 30	
12	Removing ground slabs of 'V' drain and refixing in a proper level including well packed gravel backing.	S.ft.	375	

(1) The concrete must be of jelly broken metal on small field jelly to be mixed with surki mortar.

(2) Cement plastering is to be one of cement and three of sand mixed well plastered ½" smoothened the surface neatly with pure cement, Kutin brand of cement must be used.

(3) Care must be taken to water drains for at least ten days after the drain being plastered. It should not be allowed to be dried for first ten days, but should be kept wet water in the life of cement.

P. K. DORAISAWMI AIYANGAR,
President.